Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

Name of Work: Modified Estimate For Construction of compound wall and other devolopment works at Shettihalli Subdivision office in Mallasandra,Ward No-13

Est .Cost Rs.50.00 Lakhs

No	Description of Items	No	L	B	D	Qtty	Unit	Rate	Amount
	KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.								
	For Compound wall West Side	1	9.6	1.50	1.40	20.16			
		1	9.7	1.30	1.40	17.65			
		1	9.6	1.30	1.40	17.47			
		1	10.6	1.30	1.40	19.29			
		1	1.40	1.30	1.40	2.55			
		1	5.40	1.30	1.40	9.83			
	1North Side	1	15.50	1.20	1.30	24.18			
		1	16.80	1.20	1.30	26.21			
		1	14.00	1.20	1.30	21.84			
	For Column Footings	21	1.50	1.50	1.50	70.88			
	For Main gate Columns	2	1.50	1.50	1.50	6.75			
	For Culvert	1	7.00	2.00	1.20	16.80			
	For CC Drain South Side	1	57.55	1.00	1.15	66.18			
						319.79			
	Deductions of Column footings	21	1.00	1.00	1.00	**21.00**			
					Total Modified Qty	**298.79**			
					Total Scheduled-B Qty	**340.65**			
					Qty Upto 125%	**298.79**	**Cum**	**222.04**	**66343.22**
	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No. 12/I.No.								
	For Compound wall West Side	1	9.6	1.50	0.15	2.16			
		1	9.7	1.30	0.15	1.89			
		1	9.6	1.30	0.15	1.87			
		1	10.6	1.30	0.15	2.07			
		1	1.40	1.30	0.15	0.27			
		1	5.40	1.30	0.15	1.05			
	1North Side	1	15.50	1.20	0.15	2.79			
		1	16.80	1.20	0.15	3.02			
		1	14.00	1.20	0.15	2.52			
	For Column Footings	21	1.50	1.20	0.15	5.67			
	For Main gate Columns	2	1.50	1.20	0.15	0.54			
	For CC Drain South Side	1	57.55	1.20	0.15	10.36			
						34.22			
	Deductions of Column footings	21	1.00	1.20	0.15	**3.78**			

Scanned by CamScanner

Description of Items	No	L	B	D	Qtty	Unit	Rate	Amount
				Total Modified Qty	30.44			
				Total Scheduled-B Qty	36.15			
				Qty Upto 125%	30.44	Cum	5449.98	165894.67
KSRB 5.4-4 : Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. KBS 5.1.13								
West side								
For Compound wall	1	9.6	1.30	1.00	12.48			
Above Ground level	1	9.6	1.00	2.80	26.88			
Beow Ground level	1	9.7	1.00	0.90	8.73			
Above Ground level	1	9.7	0.90	0.60	5.24			
Beow Ground level	1	9.6	1.00	0.90	8.64			
Above Ground level	1	9.6	0.90	0.60	5.18			
Beow Ground level	1	10.6	1.00	0.60	6.36			
Beow Ground level	1	10.6	0.90	0.60	5.72			
Beow Ground level	1	1.40	1.00	0.90	1.26			
Above Ground level	1	1.40	0.90	0.60	0.76			
Beow Ground level	1	5.40	1.00	0.60	3.24			
Above Ground level	1	5.40	0.90	0.60	2.92			
North Side	1	15.50	0.90	0.90	12.56			
Above Ground level	1	16.80	0.90	0.90	13.61			
For Culvert	2	7.00	0.60	0.80	6.72			
Beow Ground level	1	14.00	0.90	0.90	11.34			
					131.63			
Deductions of Column footings	21	0.90	0.90	0.90	15.31			
				Total Modified Qty	116.32			
				Total Scheduled-B Qty	54.52			
				Qty Upto 125%	68.15	Cum	6019.92	410257.55
				Qty Above 125%	48.17	Cum	6019.92	289991.59
KSRB 5.3-3 : Providing and **constructing granite / trap / basalt size stone masonry** in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13								
For Compound wall West Side	1	9.6	0.45	0.40	1.73			
	1	9.7	0.45	0.40	1.75			
	1	9.6	0.45	0.40	1.73			
	1	10.6	0.45	0.40	1.91			
	1	1.40	0.45	0.40	0.25			
	1	5.40	0.45	0.40	0.97			
North Side	1	15.50	0.45	0.40	2.79			
	1	16.80	0.45	0.40	3.02			
	1	14.00	0.45	0.40	2.52			
					16.67			
Deductions of Column footings	21	0.90	0.45	0.40	3.40			
Deductions for columns Basement	11	0.60	0.50	0.60	1.98			

Scanned by CamScanner

Description of Items	No	L	B	D	Qtty	Unit	Rate	Amount
					5.38			
				Total Modified Qty	11.29			
				Total Scheduled-B Qty	16.89			
				Qty Upto 125%	11.29	Cum	5405.40	61005.34
KSRB 4-1.5 : Providing and laying in position plain **cement concrete of mix M20** with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No. 4.5 of PWD SR 2015-16)									
For CC Drain South Side	1	57.55	0.90	0.15	7.77			
For Side Walls	2	57.55	0.15	0.90	15.54			
Column Footings	21	1.50	1.50	0.60	28.35			
Entrance Gate Column Footing	2	1.50	1.50	0.60	2.70			
Entrance Gate Column	2	0.40	0.40	2.50	0.80			
For Columnss " "Below Ground level	21	0.30	0.30	0.90	1.70			
Above Ground level	21	0.30	0.30	2.05	3.87			
				Total Modified Qty	60.73			
				Total Scheduled-B Qty	4.50			
				Qty Upto 125%	5.63	Cum	5985.36	33667.65
				Qty Above 125%	55.11	Cum	5985.36	329842.72
KSRB 4-6.4 : Providing and **removing centering, shuttering,** strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2								
or CC Drain	4	57.55		1.00	230.20			
or Coping	2	9.6		0.20	3.84			
	2	9.7		0.20	3.88			
West Side	2	9.6		0.20	3.84			
	2	10.6		0.20	4.24			
	2	1.40		0.20	0.56			
	2	5.40		0.20	2.16			
North Side	2	15.50		0.20	6.20			
	2	16.80		0.20	6.72			
	2	14.00		0.20	5.60			
lumn Footings	21	6.00		0.60	75.60			
trance Gate Column Footing	2	6.00		0.60	7.20			
r Columnss	21	1.20		0.90	22.68			
	21	1.20		2.05	51.66			
r Basement Poles	22	0.60		0.40	5.28			
				Total Modified Qty	429.66			
				Total Scheduled-B Qty	1032.66			
				Qty Upto 125%	429.66	Sqm	316.44	135961.6

Scanned by CamScanner

Description of Items	No	L	B	D	Qtty	Unit	Rate	Amount
SRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 -								
For Footing Compound Wall	210	1.90		1.55	618.45			
	210	1.90		1.55	618.45			
Columns	126	3.45		1.55	673.79			
Stirrups	480	1.50		0.39	280.80			
For Plinth	8	9.6		0.89	68.35			
	8	9.7		0.89	69.06			
	8	9.6		0.89	68.35			
	8	10.6		0.89	75.47			
	8	1.40		0.89	9.97			
	8	5.40		0.89	38.45			
Stirrups	70	1.30		0.39	35.49			
	75	1.30		0.39	38.03			
	72	1.30		0.39	36.50			
	82	1.30		0.39	41.57			
	12	1.30		0.39	6.08			
	4	1.30		0.39	2.03			
North Side Compound Wall	8	15.50		0.89	110.36			
	8	16.80		0.89	119.62			
	8	14.00		0.89	99.68			
Stirrups	120	1.30		0.39	60.84			
	125	1.30		0.39	63.38			
	110	1.30		0.39	55.77			
Entrance Gate Column Footing	20	1.90		1.55	58.90			
	20	1.90		1.55	58.90			
For Columns	16	2.90		1.55	71.92			
	34	2.00		0.39	26.52			
For CC Drain U Shape	850	2.75		0.62	1449.25			
Stright Bars	36	57.55		0.62	1284.52			
					6140.49	Kgs		
Total Modified Qty					6.14			
Total Scheduled-B Qty					6.56			
Qty Upto 125%					6.14	Tonnes	65455.56	401929.41

Scanned by CamScanner

Description of Items	No	L	B	D	Qtty	Unit	Rate	Amount
KSRB 4.2.8: Providing and laying in position **reinforced cement concrete of design mix M20** with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, and beams retaining walls, return walls, walls (any thickness) including attached plasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6. (P. No. 14/ I.No. 4.13 of CSR								
For Coping	1	9.7	0.45	0.10	0.44			
West Side	1	9.6	0.45	0.10	0.43			
	1	10.6	0.45	0.10	0.48			
	1	1.40	0.45	0.10	0.06			
	1	5.40	0.45	0.10	0.24			
North Side	1	15.50	0.50	0.10	0.78			
	1	16.80	0.50	0.10	0.84			
	1	14.00	0.50	0.10	0.70			
	1	14.00	0.50	0.10	0.70			
For Basement Poles	22	0.60	0.50	0.40	5.28			
				Total Modified Qty	9.95			
				Total Scheduled-B Qty	93.75			
				Qty Upto 125%	9.95	Cum	6650.64	66150.59
KSRB 2-4 : **Refilling available earth** around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications.								
50% of available Qtty								
				Total Modified Qty	149.39			
				Total Scheduled-B Qty	170.33			
				Qty Upto 125%	149.39	Cum	137.16	20490.98
KSRB 5-11 : Providing and **constructing load bearing wall with cement concrete cavities blocks (hollow blocks) of size 400x200x200 mm** Grade B having a minimum face shell thickness of 30mm and web thickness of 25mm with block density between 1100 kg/m3 and 1500 kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4								
	1	9.6		2.05	19.68			
	1	9.7		2.05	19.89			
	1	9.6		2.05	19.68			
	1	10.6		2.05	21.73			
	1	1.40		2.05	2.87			
	1	5.40		2.05	11.07			
					94.92			
Deduct Column Portions	21	0.3		2.05	12.92			
				Total Modified Qty	82.00			
				Total Scheduled-B Qty	105.60			
				Qty Upto 125%	82.00	Sqm	1023.84	83954.88

Scanned by CamScanner

Description of Items	No	L	B	D	Qtty	Unit	Rate	Amount
KSRB15-3.7 : Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.								
West side wall	2	9.6		2.05	39.36			
	2	9.7		2.05	39.77			
	2	9.6		2.05	39.36			
	2	10.6		2.05	43.46			
	2	1.40		2.05	5.74			
	2	5.40		2.05	22.14			
					189.83			
Columns	42	0.5		2.05	43.05			
					Total Modified Qty	**146.78**		
					Total Scheduled-B Qty	**264.20**		
					Qty Upto 125%	**146.78**	**Sqm**	**263.52**	**38679.47**
KSRB 15.10.1 Providing **white washing to new wall surface** in two coats with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications.								
Qty sama as item No -11								
					Total Modified Qty	**164.00**		
					Total Scheduled-B Qty	**264.20**		
					Qty Upto 125%	**164.00**	**Sqm**	**8.64**	**1416.96**
Providing and fabricating MS grills os as per approved drawing & Specification								
On North Side Compound Wall	1	15.50		1.90	29.45			
For Grill work	1	16.80		1.90	31.92			
	1	14.00		1.90	26.60			
					Total Modified Qty	**87.97**		
					Total Scheduled-B Qty	**110.00**		
					Qty Upto 125%	**87.97**	**Sqm**	**9144.14**	**804410.00**
Providing and fabricating MS Gates os as per approved drawing & Specification								
	2	5.00		2.35	23.50			
					Total Modified Qty	**23.50**		
					Total Scheduled-B Qty	**13.50**		
					Qty Upto 125%	**16.88**	**Sqm**	**12447.00**	**210043.13**
					Qty Above 125%	**6.63**	**Sqm**	**12447.00**	**82461.38**
For roof slab & terraces **Providing & applying water proofing** to roof slab, terraces, landscape area, podium etc., using modified polyurethane cures (conforming to ASTM C836-84) to give a tough elastomeric waterproof membrane on the surface. The surface shall be cleaned free from dust and other particle before usage. standards & methodology : This compound has a medium viscosity grade with 620% of elongation and shall be done either by roller application/brush application/ spray. This will be applied for a thickness of 1.3mm first layer 0.5mm & 2nd layer 0.8mm. After applying the 2nd layer sand sprinkle shall be done to provide								
Subdivision office	1	27.00	20.90		564.30			
Deduct Staircase portion	1	5.80	4.00		23.20			
Syntex portion	1	1.90	1.85		3.52			
					26.72			
					Total Modified Qty	**537.59**		

Scanned by CamScanner

	Description of Items	No	L	B	D	Qty	Unit	Rate	Amount
					Total Scheduled-B Qty	591.52			
					Qty Upto 125%	537.59	Sqm	756.00	406414.26
	KSRB 0.5-3.3 : Providing lime surkhi mortar of mix 1:3 (1 lime putty :3 surkhi) including cost of all materials, labour charges, HOM of machinery complete as per specifications. Specification No. KBS								
					Total Modified Qty	0.00			
					Total Scheduled-B Qty	29.58			
					Qty Upto 125%	0.00	Sqm	3061.80	0.00
	BOREWELL								
	Geophysical Investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its quality f 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging technical personal and labour required etc., as per Specification and direction								
		1				1.00			
					Total Modified Qty	1.00			
					Total Scheduled-B Qty	1.00			
					Qty Upto 125%	1.00	No	1882.00	1882.00
	Sinking Borewell of 165mm dia clear, using fast rig in all strata including over-burden upto 20mts. Fixing of casing Pipes, collars and cap with necessary cutting and threading including transportation of Rig and supporting vehicle, crew charge and cost								
	0.00 to 50.00m	1	50.00			50.00	Mtr	306.00	15300.00
	50.00 to 100.00m	1	50.00			50.00	Mtr	400.00	20000.00
	100.00 to 150.00m	1	50.00			50.00	Mtr	445.00	22250.00
	150.00 to200.00m	1	50.00			50.00	Mtr	470.00	23500.00
	200.00 to250.00m	1	50.00			50.00	Mtr	544.00	27200.00
	250.00 to300.00m	1	50.00			50.00	Mtr	583.00	29150.00
9	Supply of ISI Mark 175mm nominal Bore, Plain end steel casing Pipe-grade of steel Fee 4100 of wakk thickness 504mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel electric or basic oxygen process in fandom length o								
		1	12.00			12.00			
					Total Modified Qty	12.00			
					Total Scheduled-B Qty	32.00			
					Qty Upto 125%	12.00	mtr	1325.00	15900.00
20	Providing Borewell Collars 175mm Dia								
		3				3.00			
					Total Modified Qty	3.00			
					Total Scheduled-B Qty	5.00			
					Qty Upto 125%	3.00	Nos	150.00	450.00
21	Providing Borewell Cap 175mm Dia								
		1				1			
					Total Modified Qty	1.00			
					Total Scheduled-B Qty	1.00			
					Qty Upto 125%	1.00	Nos	100.00	100.00

Scanned by CamScanner

Description of Items	No	L	B	D	Qtty	Unit	Rate	Amount
Supply and Delivery of Galvanized Mild steel Heavy Class (B-Class) conforming to IS 1239-1979 PART-I/1979 with lastest amendments with ISI mark (one end fitted with ISI mark heavy duty collar and other end fitted with Protective cover) 50 mm dia								
	1	0.00			0.00			
					Total Modified Qty	0.00		
					Total Scheduled-B Qty	300.00		
					Qty Upto 125%	0.00	Mtrs	321.00	0.00
Providing Borewell Collars 50mm dia								
	1	0			0			
					Total Modified Qty	0.00		
					Total Scheduled-B Qty	40.00		
					Qty Upto 125%	0.00	No	125.00	0.00
Providing and Supplying Submersible Pumpset								
	1				0			
					Total Modified Qty	0.00		
					Total Scheduled-B Qty	29.58		
					Qty Upto 125%	0.00	No	50100.00	0.00
Errection Charges for Pumpset								
	1				0			
					Total Modified Qty	0.00		
					Total Scheduled-B Qty	1.00		
					Qty Upto 125%	0.00	No	3900.00	0.00
Supply an drawing3core flat PVC Submersible cable								
	1	0			0.00			
					Total Modified Qty	0.00		
					Total Scheduled-B Qty	300.00		
					Qty Upto 125%	0.00	Mtr	164.29	0.00
Supplying of LT UG Cable								
	1	0			0.00			
					Total Modified Qty	0.00		
					Total Scheduled-B Qty	15.00		
					Qty Upto 125%	0.00	Mtr	169.95	0.00
					Total Modified Qty	0.00		
					Total Scheduled-B Qty	0.00		
					Qty Upto 125%	0.00	Mtr	271.92	0.00
Supplying and fixing of class A GI Pipe of wall thickness for Ugcable								
	1	0			0.00			
					Total Modified Qty	0.00		
					Total Scheduled-B Qty	5.00		
					Qty Upto 125%	0.00	Mtr	249.26	0.00
Providing Earth Electrode								
	1				0			
					Total Modified Qty	0.00		
					Total Scheduled-B Qty	1.00		

Scanned by CamScanner

Description of Items	No	L	B	D	Qtty	Unit	Rate	Amount
	1	9.7	1.30	0.30	3.78			
	1	9.6	1.30	0.30	3.74			
	1	10.6	1.30	0.30	4.13			
	1	1.40	1.30	0.30	0.55			
	1	5.40	1.30	0.30	2.11			
1North Side	1	15.50	1.20	0.30	5.58			
	1	16.80	1.20	0.30	6.05			
	1	14.00	1.20	0.30	5.04			
For Column Footings	21	1.50	1.50	0.30	14.18			
For Main gate Columns	2	1.50	1.50	0.30	1.35			
For CC Drain South Side	1	57.55	1.00	0.30	17.27			
					68.09			
Deductions of Column footings	21	1.00	1.00	0.30	6.30			
			Total		61.79	Cum	2240.84	138463.74
Providing and Fixing **pre cast covering Slab** made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)								
	1	57.55	0.90		51.80	Sqm	1900.00	98410.50
KSRB15-13 : Applying of distemper KSRB 15-13.1 : Providing and applying one coat distemper primer of approved brand on wall surface after throughly brooming the surface to remove all dirt, dust, mortar drops and other foreign matter including preparing the surface, even and sand paper smooth, cost of materials, labour, complete as per specifications. -wall surface-								
Qtty as item No -11					164.00	Sqm	27.00	4428.00
KSRB 15-16.1 : Providing and **finishing external walls** in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.								
Qtty as item No -11					164.00	Sqm	74.52	12221.28
KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (Page No. 120 Item No. 15.74 of SR 2015-16).								
Qtty as Item no;13					222.94	Sqm	88.56	19743.57
Dismantling weather proof course and removing and conveying the debris to a distance upto 200m. (P.No. 258, I.No. 37.44 of CSR 2015-16).								
Subdivision office	1	27.00	20.90		564.30			
Deduct Staircase portion	1	5.80	4.00		23.20			
Syntex portion	1	1.90	1.85		3.52			
					26.72			
					537.59	Sqm	505.44	271716.96

Scanned by CamScanner

Description of Items	No	L	B	D	Unit	Rate	Amount
KSRRB M300- Construction of Embankment with Material Gra... KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum ... l lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) MORTH Specification No. 305							
	1	57.55	11.70	1.45	976.34	Cum	320.12	312544.
							SUB TOTAL	4622176
							Utility Shifting, Miscellaneous, Rounding off	3833.1
							Grand Total Rs	4626009

46,22,166.90

Asst Engineer
Project Division Dasarahalli
BBMP Bangalore

Asst Executive Engineer
Project Division Dasarahalli
BBMP Bangalore

Executive Engineer
Project Division Dasaraha
BBMP Bangalore

ನಂ. BBMP/CE/D2/TS/11/19-19 ದಿನಾಂಕ : 21/01/2019
ರೂ. 46:22 lakhs/- (Rs Fourty Six lakhs Twenty Thousds only)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ತಾಂತ್ರಿಕ ಸಹಾಯಕರು
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಪಾ.ಪ.ಯೋ.ಕೆ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Scanned by CamScanner